Kestrel Electric LLC

Tel (555) 0143 | Licensed & insured

11 March 2026

To: Alder Point Development

Re: Northgate Lofts Phase 2 (Job NG2-4410)

CHANGE ORDER CO-203

Status: APPROVED

Approved on 19 March 2026

Electrical rough-in revisions on Levels 2-4 per ASI-12 and RFI-231: relocate circuits, add lighting and controls, update panel schedules.

Description	Qty	Unit	Unit price	Amount
Relocate 20A branch circuits, Level 2 corridor	18	EA	$142.00	$2,556.00
1" EMT conduit and fittings	640	LF	$6.25	$4,000.00
#12 THHN copper conductor	1900	LF	$0.85	$1,615.00
Recessed LED troffer, 2x4, 40W	22	EA	$118.50	$2,607.00
Occupancy sensors, ceiling mount	9	EA	$64.00	$576.00
Junction boxes, 4-11/16 sq., with covers	31	EA	$12.40	$384.40
3/4" EMT conduit and fittings	410	LF	$4.80	$1,968.00
Fire alarm device relocation	6	EA	$88.00	$528.00
Demolition of abandoned conduit	14	HR	$71.00	$994.00

Continued on next page ...

CHANGE ORDER (continued)

Description	Qty	Unit	Unit price	Amount
Journeyman electrician labour	96	HR	$74.00	$7,104.00
Apprentice electrician labour	96	HR	$48.50	$4,656.00
Panel schedule updates and as-builts	1	LS	$650.00	$650.00
Lift rental, 3 days	3	DAY	$185.00	$555.00
Permit amendment and inspection fee	1	LS	$420.00	$420.00
			TOTAL CHANGE ORDER AMOUNT	**$28,613.40**

Schedule impact: 7 calendar days added to the contract time.

Related documents: ASI-12, RFI-231, Subcontract E-4410-07

Requested by: Marcus Hale (Alder Point)

Approved by: Elaine Brandt Date: 19 Mar 2026

Signature: *Elaine Brandt*

Retainage of 10% will be withheld per the subcontract. A conditional lien waiver is required with the next pay application.