CHANGE ORDER

Change Order No.: CO-052

STATUS: PENDING

Date Issued: June 3, 2026
Project: Eastgate Distribution Center
Project No.: EDC-77
Owner / GC (To): Northfield GC Services
Contractor (From): Summit Roofing & Sheet Metal Inc.

Description of change

Roof drawings omitted flashing at the rooftop unit curbs; replace damaged membrane and add crickets and counterflashing.

Description	Qty	Unit	Unit price	Amount
Replace damaged TPO membrane at RTU curbs	640	SF	$11.50	$7,360.00
Tapered insulation crickets	12	EA	$245.00	$2,940.00
Sheet metal counterflashing	210	LF	$18.50	$3,885.00
			Subtotal	$14,185.00
			Sales tax (7%)	$992.95
			TOTAL CHANGE ORDER AMOUNT	**$15,117.95**

Schedule impact: 5 calendar days

Requested by: Wes Kowalczyk
Approved by: _____ Date: _____
Signature: _____

Retainage of 10% will be withheld per the subcontract. A conditional lien waiver is required with the next pay application.